


## VICINITY PLAN NOT TO SCALE


# NON-RESIDENTIAL SITE PLAN MIARA TRANSPORTATION

MAP 136 LOT 1 12 BOCKES ROAD HUDSON, NEW HAMPSHIRE


OWNER/APPLICANT:
JOSEPH A. MIARA JR., TRUSTEE
GRANITE REALTY TRUST
12 BOCKES ROAD
HUDSON, NEW HAMPSHIRE 03051

PREPARED BY:
KEACH-NORDSTROM ASSOCIATES, INC.
10 COMMERCE PARK NORTH, SUITE 3
BEDFORD, NEW HAMPSHIRE 03110
(603) 627-2881









KEACH-NORDSTROM ASSOCIATES, INC.


Civil Engineering Land Surveying Landscape Architecture


10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881


MAY 20, 2024 PROJECT NO. 16-0223-1


HUDSON  ROBINSON POND ROAD  RO	SITE  ROLLING WOODS DRIVE  ROLLING WOODS DRIVE  ROAD  ROAD  ROAD  ROAD  ROAD  ROAD  ROAD  ROAD  ROAD
	3 PLAN 1"=1,000'


SHEET TITLE	SHEET No.
OVERVIEW PLAN	<b>1</b>
EXISTING CONDITIONS PLAN	2
REMOVALS/DEMOLITION PLAN	3
NON-RESIDENTIAL SITE LAYOUT PLAN	4
GRADING, DRAINAGE & UTILITY	5
LANDSCAPE PLAN	6
CONSTRUCTION DETAILS	7-8




















(MARCH 2008)

VARIES

**ELEVATION** 

CROSS-SECTION

STONE CHECK DAM DETAIL

NOT TO SCALE

(MARCH 2008)

PURSUANT TO APPROVED BY THE HUDSON, NH PLANNING BOARD

YEAR FROM DATE MEETING FINAL APPROVAL. FINAL APPROVAL COMMENCES AT THE PLANNING

SITE PLANS ARE VALID FOR ONE YEAR FROM THE DATE OF PLANNING BOARD

BOARD MEETING DATE AT WHICH THE PLAN RECEIVES FINAL APPROVAL.

DATE OF MEETING:

2" - 3" COARSE

AGGREGATE

STONE (TYP.)

THE SITE REVIEW

REGULATIONS OF

THE HUDSON

THE SITE PLAN

APPROVAL

GRANTED HEREIN

EXPIRES ONE

PLANNING BOARD. SIGNATURE

#### **CONSTRUCTION SPECIFICATIONS:**

- 1. THE GEOTEXTILE FABRIC SHALL MEET THE DESIGN CRITERIA FOR SILT FENCES.
- 2. THE FABRIC SHALL BE EMBEDDED A MINIMUM OF 8 INCHES INTO THE GROUND AND THE SOIL COMPACTED OVER THE EMBEDDED FABRIC.
- 3. WOVEN WIRE FENCE SHALL BE FASTENED SECURELY TO THE FENCE POSTS WITH WIRE TIE OR STAPLES WHERE NOTED OR AS DIRECTED BY DESIGN ENGINEER
- 4. FILTER CLOTH SHALL BE FASTENED SECURELY TO THE WOVEN WIRE FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP, MIDSECTION AND BOTTOM.
- 5. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED AND
- 6. FENCE POSTS SHALL BE A MINIMUM OF 36 INCHES LONG AND DRIVEN A MINIMUM OF 16 INCHES INTO THE GROUND. WOOD POSTS SHALL BE OF SOUND QUALITY HARDWOOD AND SHALL HAVE A MINIMUM CROSS SECTIONAL AREA OF 3.0 SQUARE
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT

#### MAINTENANCE:

- SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE
- 2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE. THE FABRIC SHALL BE REPLACED PROMPTLY.
- 3. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE
- 4. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

**CONCRETE BLOCK** 

MATS/BLANKETS SHOULD BE **INSTALLED VERTICALLY** DOWNSLOPE AND SHALL BE DOUBLE NET COCONUT BIODEGRADABLE ROLLED **EROSION CONTROL BLANKET BY** EAST COAST EROSION CONTROL, OR APPROVED EQUAL MINIMUM 4 (100mm) OVERLAP (40mm) 0.14 STAPLES ISOMETRIC VIEW 4'-0" (1.2m) SLOPE SURFACE SHALL BE FREE OF ROCKS. CLODS, STICKS AND GRASS. MATS/ BLANKETS SHALL HAVE GOOD SOIL CONTACT. 2. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS. 3. LAY BLANKETS LOOSELY AND STAKE OR STAPLE

**EROSION CONTROL BLANKETS - SLOPE INSTALLATION** 

NOT TO SCALE

(AUGUST 2011)

**EROSION CONTROL BLANKETS - SWALE INSTALLATION NOT TO SCALE** 

(MARCH 2008)

## BURY THE TOP END OF THE JUTE STRIPS IN A TRENCH 6 INCHES OR MORE IN DEPTH. 2. TAMP THE TRENCH FULL OF SOIL. SECURE WITH ROW OF STAPLES, 6 INCH SPACING, 4 INCHES DOWN FROM THE TRENCH. OVERLAP: BURY UPPER END OF LOWER STRIP AS IN "A" AND "B". OVERLAP END OF TOP STRIP 4 INCHES AND STAPLE. 4. EROSION STOP: FOLD OF INCH CENTERS) JUTE BURIED IN SILT TRENCH AND TAMPED: DOUBLE ROW OF STAPLES. ON 2 INCH CENTERS TYPICAL STAPLES No. 11 GAUGE WIRE

#### CONSTRUCTION SEQUENCE

- FIRST CUT AND CLEAR TREES AND BRUSH ONLY WITHIN DESIGNATED LIMITS OF CLEARING AS NECESSARY TO FACILITATE PROPOSED CONSTRUCTION. ALL TREES, BRANCHES AND OTHER VEGETATIVE MATERIALS SHALL BE PROPERLY DISPOSED OF OFF SITE BY THE CONTRACTOR. THIS PROJECT IS MANAGED TO MEET THE
- REQUIREMENTS AND INTENT OF RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES. PRIOR TO COMMENCEMENT OF ANY EARTHMOVING OPERATIONS, ALL APPLICABLE TEMPORARY EROSION CONTROL MEASURES, INCLUDING SPECIFIED PERIMETER SILTATION FENCING AND STABILIZED CONSTRUCTION EXIT SHALL BE IN PLACE AS SHOWN ON THE PROJECT PLANS.
- 3. COMPLETE GRUBBING OPERATIONS. ALL STUMPS AND SIMILAR ORGANIC DEBRIS SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR. NATIVE ORGANIC SOIL MATERIALS SUITABLE FOR USE AS TOPSOIL SHALL BE STOCKPILED WITHIN AREAS OUT OF THE WAY OF OTHER CONSTRUCTIONS ACTIVITIES AND DRAINAGE FLOW. STOCKPILES SHALL BE TEMPORARILY SEEDED WITH WINTER RYE AND BE SURROUNDED WITH HAY BALES AND/OR FABRIC SILTATION FENCE IN ORDER TO PREVENT LOSS DUE TO EROSION.
- 4. BEGIN EARTHMOVING OPERATIONS, COMMENCING WITH WORK NEEDED TO BALANCE SITE AND FACILITATE BUILDING FOUNDATION AND RETAINING WALL CONSTRUCTION. PERMANENT DOWNSLOPE WORK SHALL BE PROTECTED FROM UPGRADIENT STORMWATER FLOW BY THE CONSTRUCTION OF TEMPORARY EARTHEN DIKES OR
- 5. ONCE BUILDING FOUNDATION WORK IS UNDERWAY, CONTINUE EARTHMOVING OPERATIONS UNTIL DESIGN SUBGRADE IS ACHIEVED.
- 6. INSTALL DRAINAGE SWALE SYSTEMS AND OTHER UTILITIES WORKING FROM LOW TO HIGH. INCOMPLETE WORK SHALL BE PROTECTED FROM SILTATION BY THE USE OF SILTATION BARRIERS AROUND SWALES UNTIL THE SITE HAS
- BECOME FULLY STABILIZED. 7. PLACE GRAVEL AND CRUSHED GRAVEL OVER PROPOSED DRIVEWAY, WALKS AND PARKING AREAS AND COMPACT
- IN SPECIFIED LIFT THICKNESS. COMPLETE EXCAVATION/STABILIZATION GRADING ACTIVITIES. WHEN COMPLETE, IMMEDIATELY BEGIN TOPSOILING PROPOSED TURF AREAS USING STOCKPILED LOAM SUPPLEMENTED WITH BORROW LOAM, IF NECESSARY, TO
- LEAVE A THICKNESS OF 4 INCHES OF FRIABLE LOAM. 9. FINE GRADE ALL FUTURE TURF AREAS AND HYDROSEED WITH THE SPECIFIED SEED MIXTURE IMMEDIATELY AFTER 4 INCH OVERLAP OF JUTE FINE GRADING IS COMPLETED. ALL AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISH GRADE.
- STRIPS WHERE TWO OR 10. INSTALL THE BINDER COURSE OF PAVEMENT OVER ALL DESIGNATED AREAS. MORE STRIP WIDTHS ARE 11. CONTINUE TO MONITOR AND RECTIFY MINOR SITE AND SLOPE EROSION UNTIL ENTIRE SITE APPEARS TO BE REQUIRED (STAPLE ON 18 COMPLETELY STABILIZED AND VEGETATED WITH A HEALTHY STAND OF TURF OR GROUND COVER. MAINTAIN
  - SPECIFIED SILTATION/EROSION CONTROL MEASURES THROUGH ONE WINTER.
  - 12. INSTALL THE SPECIFIED WEARING COURSE OF PAVEMENT OVER THE BINDER COURSE. 13. COMPLETE INSTALLATION OF LANDSCAPING, SIGNAGE AND OTHER SITE AMENITIES.

#### STAPLE OUTSIDE EDGE EROSION CONTROL NOTES

- EXPOSED EARTHWORK SHALL BE CONFINED TO AS LIMITED AN AREA AS IS PRACTICAL AT ANY GIVEN TIME THROUGHOUT THE CONSTRUCTION SEQUENCE. AT NO TIME SHALL MORE THAN FIVE (5) ACRES OF SITE AREA BE IN AN UNSTABLE CONDITION. NO GIVEN AREA OF THE SITE SHALL BE LEFT IN AN UNSTABILIZED CONDITION FOR A
- PERIOD OF TIME EXCEEDING THIRTY (30) CALENDAR DAYS. TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED IN STRICT ACCORDANCE WITH PROJECT PLANS. IN ADDITION, SIMILAR MEASURES SHALL BE INSTALLED WHERE AND WHEN THE FIELD CONDITION, OR FIELD OPERATION OF THE INDIVIDUAL SITE CONTRACTOR, MAY WARRANT. ALL TEMPORARY EROSION CONTROL MEASURES USED SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25" OF RAINFALL OR MORE. THEY SHALL BE CLEANED AND MAINTAINED AND OTHERWISE KEPT IN AN EFFECTIVE OPERATING MANNER THROUGHOUT THE CONSTRUCTION PERIOD.
- ALL DISTURBED AREAS DESIGNATED TO BE TURF, SHALL RECEIVE A MINIMUM APPLICATION OF 4 INCHES OF LOAM (COMPACTED THICKNESS), PRIOR TO FINAL SEEDING AND MULCHING.
- ALL SWALES AND DITCHLINES SHALL BE PERIODICALLY CLEANED OF DEPOSITED SEDIMENT SO AS TO MAINTAIN AN EFFECTIVE GRADE AND CROSS SECTION. ALL SWALES AND DITCHLINES SHALL BE FULLY STABILIZED PRIOR TO HAVING STORMWATER DIRECTED TOWARDS THEM.
- IN THE EVENT THAT, DURING CONSTRUCTION OF ANY PORTION OF THIS PROJECT, A WINTER SHUTDOWN IS NECESSARY. THE CONTRACTOR SHALL STABILIZE ALL INCOMPLETE WORK AND PROVIDE FOR SUITABLE METHODS
- OF DIVERTING RUNOFF IN ORDER TO ELIMINATE SHEET FLOW ACROSS FROZEN SURFACES. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
- A. BASE COURSE GRAVELS ARE INSTALLED IN AREAS TO BE PAVED: B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
- C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED; OR EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- DUST SHALL BE CONTROLLED BY THE USE OF WATER AS NECESSARY THROUGHOUT THE CONSTRUCTION PERIOD, IN ACCORDANCE WITH ENV-A 100n 8. IN NO WAY ARE THOSE TEMPORARY EROSION CONTROL MEASURES INDICATED ON THESE PLANS TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGEMENT IN INSTALLING SUPPLEMENTARY
- EROSION CONTROL MEASURES WHERE AND WHEN SPECIFIC SITE CONDITIONS AND/OR CONSTRUCTION METHODOLOGIES MAY WARRANT 9. AREAS HAVING FINISH GRADE SLOPES OF 3: 1 OR STEEPER, SHALL BE STABILIZED WITH JUTE MATTING WHEN AND IF FIELD CONDITIONS WARRANT, OR IF SO ORDERED. JUTE MATTING INSTALLED TO CONFORM WITH THE
- RECOMMENDED BEST MANAGEMENT PRACTICE OUTLINED IN VOLUME 3 OF THE NEW HAMPSHIRE STORMWATER MANUAL "EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION."
- 10. ALL DETENTION PONDS AND TREATMENT SWALES SHALL BE CONSTRUCTED PRIOR TO ANY EARTH MOVING ACTIVITIES THAT WILL INFLUENCE STORMWATER RUNOFF.
- 11. ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. 12. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

#### WINTER CONSTRUCTION NOTES:

- ALL PROPOSED POST-DEVELOPMENT VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 4:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE PLACEMENT OF EROSION CONTROL BLANKET'S OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR
- ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL
- BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS. 3. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3 OR, IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON, BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT.
- AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: A. BASE COURSE GRAVELS ARE INSTALLED IN AREAS TO BE PAVED;
  - B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED:
  - C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED: OR D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

# - GRAVEL FILTER ----WIRE SCREEN FILTERED WATER

WIRE SCREEN-

SIGNATURE DATE \_

SIGNATURE DATE

RUNOFF WATER \_\_

1. CONCRETE BLOCKS SHOULD BE PLACED LENGTHWISE ON THEIR SIDES IN A SINGLE ROW AROUND THE PERIMETER OF THE INLET. THE ENDS OF EACH BLOCK SHOULD BE ABUTTING. THE HEIGHT OF THE BARRIER CAN BE VARIED DEPENDING ON THE DESIGN BY STACKING VARIOUS COMBINATIONS OF DIFFERENT SIZED BLOCKS. THE BARRIER SHOULD BE A MINIMUM OF 12 INCHES HIGH AND A MAXIMUM OF 24 INCHES HIGH.

WITH GRATE

- HARDWARE CLOTH OR WIRE MESH SHOULD BE PLACED OVER OPENINGS OF THE CONCRETE BLOCKS AND EXTENDED AT LEAST 12 INCHES AROUND THE OPENING TO PREVENT AGGREGATE FROM BEING TRANSPORTED THROUGH THE OPENINGS IN THE BLOCK.
- 3. SEWER STONE OR OTHER CLEAN COARSE AGGREGATE SHOULD BE PLACED AGAINST THE BLOCK TO THE TOP OF THE BARRIER.

#### BLOCK & GRAVEL DROP INLET SEDIMENT FILTER

NOT TO SCALE (MARCH 2008)

## TURF ESTABLISHMENT SCHEDULE

TO MAINTAIN DIRECT CONTACT WITH THE SOIL.

TO ESTABLISH AND MAINTAIN PERMANENT AND TEMPORARY TURF AREAS, RESTORE GROWTH TO EXISTING TURF AREAS DISTURBED DURING CONSTRUCTION AND CONTROL SOIL EROSION

#### PREPARATION AND EXECUTION:

- RAKE THE SUBGRADE OF ALL AREAS TO BE LOAMED AND SEEDED TO REMOVE RUBBISH.
- STICKS, ROOTS AND STONES LARGER THAN 1 INCH. PLACE LOAM OVER AREAS TO BE SEEDED AND SPREAD.
- FINE GRADE SURFACE AND SUPPLEMENT WITH SUITABLE LOAM WHERE NEEDED. TO CREATE A UNIFORM SURFACE ACCORDING TO THE FINISH GRADES INDICATED; TOP AND BOTTOM OF SLOPES SHALL BE ROUNDED. NO LOAM SHALL BE SPREAD IF THE SUBGRADE IS EXCESSIVELY WET OR FROZEN APPLY LIME EVENLY OVER LOAM SURFACE AND THOROUGHLY INCORPORATE LIME INTO
- APPLY FERTILIZER AND MIX WITH THE UPPER 2 INCHES OF LOAM. 6. DETERMINE APPROPRIATE MIXTURE FOR AREA TO BE SEEDED BASED ON EXAMINATION OF PROJECT PLANS. UNIFORMLY SPREAD THE SEED BY BROADCASTING OR HYDROSEEDING. IF BROADCASTING, LIGHTLY RAKE INTO THE PREPARED SURFACE AND

THE LOAM BY HEAVY RAKING TO AT LEAST ONE-HALF THE DEPTH OF THE LOAM.

AFTER SEED IS SPREAD, WATER THOROUGHLY WITH A FINE SPRAY. SEEDING FOR PERMANENT COVER SHALL OCCUR BETWEEN SEPTEMBER 15 AND OCTOBER 15 AND BETWEEN APRIL 15 AND JUNE 15. SEEDING SHALL NOT BE DONE DURING WINDY WEATHER, WHEN THE GROUND IS FROZEN OR EXCESSIVELY WET OR

ROLL. IF, HYDROSEEDING, USE 4 TIMES THE RECOMMENDED RATE OF INOCULANT.

8. WITHIN 24 HOURS AFTER SEEDING OPERATION, UNIFORMLY MULCH THE AREA WITH HAY. ANCHOR MULCH ON ALL SLOPES EXCEEDING 3 : 1 USING MULCH NETTING INSTALLED IN ACCORDANCE WITH THE MANUFACTURER.

PROTECT AND PREVENT AGAINST WASHOUTS, ANY WASHOUTS WHICH OCCUR SHALL BE

PROMPTLY REGRADED AND RESEEDED. 10. WHEN IT IS IMPRACTICAL TO ESTABLISH PERMANENT GROWTH ON DISTURBED EARTH BY OCTOBER 15, A TEMPORARY SEED MIXTURE SHALL BE USED. WHEN TEMPORARY SEEDING CANNOT ESTABLISH VISIBLE GROWTH, THE DISTURBED AREA SHALL BE

#### COVERED WITH SIX INCHES OF MULCH FOR THE WINTER. MAINTENANCE:

ALL SEEDED AREAS SHALL BE KEPT WATERED AND IN GOOD CONDITION. RESEED AS NECESSARY TO ESTABLISH HEALTHY UNIFORM GROWTH OVER THE ENTIRE SEEDED AREA. MAINTAIN SEEDED AREAS IN AN APPROVED CONDITION UNTIL FINAL ACCEPTANCE. MAINTENANCE SHALL INCLUDE REPAIRS FOR DAMAGE CAUSED BY EROSION.

#### LOAM SHALL BE APPLIED AT A MINIMUM COMPACTED THICKNESS OF 4 INCHES.

#### **APPLICATION RATES:**

OTHERWISE UNTILLABLE

- LIME SHALL BE APPLIED AT A RATE OF 75 TO 100 POUNDS PER 1,000 S.F. FERTILIZER SHALL BE APPLIED AT A RATE OF 30 POUNDS PER 1,000 S.F.
- SEED MIXTURE FOR LAWN AREAS SHALL BE APPLIED AT A RATE OF AT LEAST 80 POUNDS PER ACRE OR 2 POUNDS PER 1,000 S.F.
- TEMPORARY SEED MIXTURE SHALL BE APPLIED AT A RATE OF 2 POUNDS PER 1,000 S.F. SEED MIXTURE FOR SLOPE AREAS SHALL BE APPLIED AT A RATE OF 80 POUNDS PER
- ACRE OR 2 POUNDS PER 1,000 S.F. SEED MIXTURE FOR STORMWATER MANAGEMENT AREAS SHALL BE APPLIED AT A RATE
- OF 70 POUNDS PER ACRE OR 1.6 POUNDS PER 1,000 S.F. 8. MULCH SHALL BE APPLIED AT A RATE OF 90 POUNDS PER 1,000 S.F.

#### **MATERIALS**:

- 1. LOAM USED FOR TOPSOIL SHALL BE FRIABLE, FERTILE, NATURAL FREE-DRAINING LOAM FREE OF ROOTS, GRASS, STICKS, WEEDS, CLAY, SOD LUMPS, DEBRIS AND STONES LARGER THAN 1 INCH IN ANY DIMENSION. SOIL SHALL NOT BE EXCESSIVELY ACID OR ALKALINE AND CONTAIN NO TOXIC MATERIALS.
- 2. LIME SHALL BE GROUND LIMESTONE CONTAINING NO LESS THAN 95% CALCIUM AND MAGNESIUM CARBONATES.
- FERTILIZER SHALL BE 10-20-20 COMMERCIAL GRADE.
- 4. SEED MIXTURE FOR LAWN AREAS SHALL BE 99% PURE LIVE SEED AND CONSIST OF THE
- **FOLLOWING** 25% CREEPING RED FESCUE 25% KENTUCKY BLUEGRASS 25% REDTOP
- 25% MANHATTAN PERENNIAL RYEGRASS TEMPORARY SEEDING MIXTURE SHALL BE AN APPROVED CONSERVATION MIX OR CONSIST OF THE FOLLOWING:
  - 15% BLACKWELL OR SHELTER SWITCHGRASS 30% NIAGRA OR KAW BIG BLUESTEM
  - 30% CAMPER OR BLAZE LITTLESTEM 15% NE-27 OR BLAZE SAND LOVEGRASS

10% VIKING BIRDSFOOT TREFOIL

- INOCULUM SPECIFIC TO BIRDSFOOT TREFOIL MUST BE USED WITH THIS MIXTURE. IF SEEDING BY HAND, A STICKING AGENT SHALL BE USED. IF SEEDING WITH A HYDROSEEDER, USE FOUR TIMES THE RECOMMENDED AMOUNT OF INOCULUM. SEED MIXTURE FOR SLOPE AREAS SHALL BE 99% PURE LIVE SEED AND SHALL CONSIST
- OF THE FOLLOWING: 30% CREEPING RED FESCUE 40% PERENNIAL RYE GRASS 15% REDTOP

15% CREEPING BENTGRASS

10% FLATPEA

- 15% BIRDSFOOT TREFOIL \*IN ADDITION TO THE MIX SPECIFIED ABOVE, CROWN VETCH SHALL BE USED ON ALL SLOPES STEEPER THAN 3 : 1. CROWN VETCH SHALL BE APPLIED AT A RATE OF 10 POUNDS PER ACRE AND INOCULUM SPECIFIC TO CROWN VETCH MUST BE
- SEED MIXTURE FOR STORMWATER MANAGEMENT AREAS, INCLUDING DETENTION BASINS AND VEGETATED TREATMENT SWALES SHALL CONSIST OF THE FOLLOWING: 25% CREEPING RED FESCUE
  - 15% SWITCH GRASS 15% FOX SEDGE
- 20% WILDFLOWER VARIETY 8. HAY USED FOR MULCH SHALL CONSIST OF MOWED AND PROPERLY CURED GRASS OR LEGUME MOWINGS, FREE FROM WEEDS, TWIGS, DEBRIS OR OTHER DELETERIOUS MATERIAL AND ROT OR MOLD.

## **CONSTRUCTION DETAILS**

#### MIARA TRANSPORTATION MAP 136 LOT 1

12 BOCKES ROAD

HUDSON, NEW HAMPSHIRE HILLSBOROUGH COUNTY

#### JOSEPH A. MIARA JR., TRUSTEE 12 BOCKES ROAD

GRANITE REALTY TRUST HUDSON, NH 03051 H.C.R.D. BK. 8410 PG. 2473

OWNER OF RECORD:


JOSEPH A. MIARA JR., TRUSTEE GRANITE REALTY TRUST 12 BOCKES ROAD HUDSON, NH 03051

APPLICANT:



. KEACH-NORDSTROM ASSOCIATES. INC.

Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881



 REVISIONS				
No.	DATE	Dì	ESCRIPTION	В
ļ				_
				_
				-
				_
<b>DATE:</b> MAY 20, 2024		SCALE: AS SHOWN		
PRO.	JECT NO: 16	5-0223-1	SHEET 8 OF 8	-